

Sawdust and Septic Systems the Final Chapter

George Heufelder, M.S., R.S.
Massachusetts Alternative Septic System
Test Center
Barnstable County Department of Health
and Environment

Or...



- *How certain lignolytic enzymes free the carbon in cellulosic materials to subsequently provide carbon for the denitrification of percolating wastewater from onsite septic system soil treatment units.*

This project has been financed with Federal Funds from the Environmental Protection Agency (EPA) to the Massachusetts Department of Environmental Protection (the Department) under an s. 319 competitive grant. The contents do not necessarily reflect the views and policies of EPA or of the Department, nor does the mention of trade names or commercial products constitute endorsement or recommendation for use.






Or.....

Saws 4 – the final Chapter

*Just when you thought it was
safe to go back into the woods*

George Heufelder, M.S., R..S.
Massachusetts Alternative Septic System Test Center
Barnstable County Department of Health and Environment

Background



Due to the impact of nitrogen from onsite septic systems, the State of Florida funded research on non-proprietary “passive” means to remove nitrogen from onsite wastewater systems using lignocellulose (sawdust and woodchips) integrated into the soil treatment areas (a.k.a. Leachfields)



We set as our goal

To examine all elements of successful non-proprietary onsite denitrification projects and determine how to adjust the design features to work in our particular climatological and geological setting.

To determine whether the principles used in these projects will allow a design that is economical and feasible to install in coastal settings.



Collaborative Effort

- Barnstable County Department of Health and Environment and MASSTC
- Damann L. Anderson, P.E., a researcher of passive nitrogen removal systems for the State of Florida Onsite Sewage Nitrogen Reduction Study (FOSNRS);
- George Loomis, an onsite septic system specialist and published author from the University of Rhode Island;
- Following work by Dr. Will Robertson of the University of Waterloo;
- Jose Amador and Sara Wiggington at the University of Rhode Island;
- More recently, researchers at Stony Brook University, NY




Three promising designs

Simple “layer cake”



Lined “layer cake”

“Box” system

The background of the slide is a close-up, high-resolution image of a wood grain. The wood is a warm, reddish-brown color, with prominent, wavy, concentric growth rings that create a sense of depth and texture. The lighting is soft, highlighting the natural grain patterns and the slight undulations of the wood surface.

Simple layering
An intuitively easier and
less expensive option

Simple layering





Lysimeter
port

Lysimeter
port

Sand (nitrification layer) placement

Sand:Sawdust (denitrification) Layer






Principle of Operation

STANDARD SEPTIC SYSTEM

Septic tank effluent goes to leachfield

Nitrogen converts to nitrate (nitrification)

Nitrate goes to embayment





LAYERED SEPTIC SYSTEM


Septic tank effluent goes to leachfield

Nitrogen converts to nitrate (nitrification)

Nitrate is reduced to nitrogen gas (denitrification)




But will it work?




“Everything should be made as simple as possible, but not simpler”


keeping it Simple




MASSTC (test center)venue




MASSTC (test center)venue



MASSTC (test center)venue



MASSTC (test center)venue




**What about
the
Real World ?**


vs. Test Center Studies



Westport Residence - Year Round - 2 Occupants




Westport Year-Round Residence – Two adult occupants



Only 4 months of data

Acushnet Residential - 3 person year-round - 212 gal/day




50% Removal

19 mg/L

● Septic Tank Effluent - TN ● Acushnet-Sawdust - TN ● Sand-Control - TN

Westport Year-Round Residence – Two adult occupants



18 months of data

Seasonal Use

Treated Portion of Soil Absorption System

Un-Treated (Control) Portion of Soil Absorption System

Septic tank effluent

Septic tank effluent

104 mg/L

104 mg/L

18" ASTM C-33 SAND

88.6% removal

18" ASTM C-33 SAND


55.7% removal

18" ASTM C-33 SAND & WOODCHIPS

18" ASTM C-33 SAND


11.9 mg/L

46.0mg/L



Major Findings - simple layering approach


- Cold weather impacts performance – Below 10° C (50°F) denitrification slows. Removal rates are reduced to 40 – 50%.
- We have still not determined the mechanism that slows performance to enhance cold-weather denitrification.
- Nitrification (the precursor of denitrification) does not seem to be appreciably reduced in soils-based systems (but does slow a bit below 5° C)
- Residence time matters (higher hydraulic loading – lower performance especially in cold weather)



If you're in Florida, there is probably little impact by temperature 😊

Source: STATE OF FLORIDA DEPARTMENT OF HEALTH CHAPTER 64E-6, FLORIDA ADMINISTRATIVE CODE - STANDARDS FOR ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEMS.

Allowed



PART 2




Saturation may be
the key to stable
denitrification


Two saturated designs show promise and are being installed under various demonstration projects



Layered, lined soil treatment system cross section







Unsaturated, Lined Nitrification System Cross Section (not to scale)




Both saturated designs require an additional soil treatment area for final disposal






SOIL TREATMENT AREA 2



4 Bedroom Design



SOIL TREATMENT AREA 2



	Design 1 Layered system with saturated denitrification layer	Design 2 Layered system with no containment liner	Design 3 Contained nitrification bed followed by a contained woodchip bioreactor	Standard Gravity System	Standard system requiring a pump
Septic Tank, pump chamber and Installation	\$8,500	\$8,500	\$8,500	\$3,500	\$8,500
Pressure distribution means/piping	\$1,500	\$1,500	\$1,500	\$500	\$500
Excavation leachfield	\$2,600	\$3,600	\$1,500	\$1,750	\$1,750
Sand	\$1,500	\$1,500	\$950	\$1,700	\$1,700
Gravel	\$250	\$200	\$250	\$1,000	\$1,000
Miscellaneous	\$1,000	\$1,000	\$1,000	\$1,000	\$1,000
Pump and wiring	\$600	\$600	\$600		\$600
Control Panel and wiring	\$900	\$900	\$900		\$900
Containment Liner and piping	\$600		\$600		
Containment tank and piping			\$2,500		
Sawdust	\$400	\$400			
Woodchips			\$300		
Soil Treatment Area 2 ^{**}	\$3,500		\$3,500		
Total Costs	\$21,350	\$18,200	\$22,100	\$9,450	\$15,950

Where to now?

- Further experiments with unsaturated design
- Installation and testing of “box” saturated design
- Enhancement experiments to find ways to overcome diminished winter performance
- Research the findings in Florida, Long Island, Connecticut and anywhere else these systems are allowed
- Continue to research ways to bring down costs
- Anything else that comes to mind

Questions?

